
Appendix A Vicinity and Site Maps

MILLIE'S DEVELOPMENT & EAGLE SUBDIVISION VICINITY MAP

28441 ID-57 PRIEST LAKE, ID 83856

SECTION 25, TOWNSHIP 60 NORTH, RANGE 5 WEST. BOISE MERIDIAN.





ENGINEER'S STAMP





INISION BUT SOME A SOUR AND ASSOCIATED LILL CONSULTING ENGINEERS SOURCE (509) 447-3626 (509)

ENGINEER'S STAMP

SHEET TILE:

SITE PLAN


PROJECT:
MILLIE'S DEVELOPMENT AND EAGLE SUBDIVISION


PRIEST LAKE, ID 83856

DATE: 10-19-22
SCALE: NTS
DRAWN BY: KAK
CHECKED BY: KAK
FILE NAME.: APPROACH
VICINITY MAP
DATA No.; 3420-20-001

SHEET 2 OF 2

SITE PLAN











EAGLE SUBDIVISION & MILLIE'S DEVELOPMENT STATE HIGHWAY 57 IMPROVEMENTS

PRIEST LAKE, BONNER COUNTY, IDAHO




SHEET INDEX				
SHEET #	SHEET TITLE			
C1	COVER SHEET AND DRAWING INDEX			
R2	EXISTING HIGHWAY 57 PLAN VIEW			
R3	PROPOSED HIGHWAY 57 IMPROVEMENTS, 0+00 - 6+00			
R4	PROPOSED HIGHWAY 57 IMPROVEMENTS, 6+00 - 12+00			
R5	HIGHWAY CROSS SECTIONS, 0+00 - 6+00			
R6	HIGHWAY CROSS SECTIONS, 6+50 - 12+00			
R7	HIGHWAY 57 APPROACH PROFILES			
R8	PERMANENT TRAFFIC CONTROL/SIGNAGE PLAN			
R9	ROAD CONSTRUCTION DETAILS			
R10	ROAD AND STORMWATER DETAILS			
R11	TRAFFIC CONTROL PLAN			
R12	TEMPORARY EROSION & SEDIMENT CONTROL PLAN			



CHECKED BY:

SHEET C1 OF 12



ENGINEER'S STAMP

NGINEERS
GTON, 99156

1 5/30 REVISED ENTRANCE ROADDLO/KAK
No. DATE REVISION DEN/CHK


AN DE STATE OF THE STATE OF THE


TING PLAN VIEW, HIGHWAY 57
ECT:
E HIGHWAY 57 ACCESS IMPROVEMENTS
E PUD & MILLIE'S DEVELOPMENT PROJECT 2023


DATE: 12-15-22
SCALE: AS SHOWN
DRAWN BY: KAR


DRAWN BY: KAK
CHECKED BY: KAK
FILE NAME: HIGHBUY 57 NT rl
DATA No.: 13420-20-001


SHEET R2 OF 12






































0 30 60 HORIZONTAL SCALE IN FEET

RELEASE FOR REVIEW

0+00 TO 6+00
SESS IMPROVEMENTS
COUNTY, IDAHO

Jens J

9156

HIGHWAY 57 SECTIC PROJECT: STATE HIGHWAY 57 EAGLE PUD & MILLIE


DATE: 12-15-22
SCALE: AS SHOWN
DRAWN BY: KAK
CHECKED BY: KAK
FILE NAME: HORMON 57 NT of


DATA No.: 13420-20-001


SHEET R5 OF 12


NOTES FOR THIS DETAIL


- (N1) EXISTING GROUND SURFACE
- N2 PROPOSED FINISHED SURFACE
- (N3) PROPOSED APPROACH REGENT SQUARE DRIVE
- (N4) AREA OF HIGHWAY WIDENING
- N5) EMBANKMENT CONSTRUCTION PER ITD SPECIFICATION SECTION 205
- N6 BENCH EMBANKMENT INTO EXISTING SLOPE MINIMUM VERTICAL CUT 24-INCHES MINIMUM HORIZONTAL WIDTH 6-FT.
- (N7) EXISTING PRIEST LAKE SERVICE CENTER APPROACH, PROTECT
- (N8) EXISTING DRIVEWAY APPROACH, PROTECT
- N9 PROPOSED STORMWATER DRAINAGE SWALE/DITCH



































RELEASE FOR REVIEW



ELLASS NEWPORT, WASHINGTON, 99156

(509) 447–3626

REVISED ENTRANCE ROA

REVISED ENTRANCE ROA


REVISED ENTRANCE ROA

1WAY 57 ACCESS IMPROVEMENTS
& MILLIE'S DEVELOPMENT PROJECT 20

EL LISTO DATE: 12-15-22
SCALE: AS SHOWN
DRAWN BY: KAK

DRAWN BY: KAK
CHECKED BY: KAK
FILE NAME: HOSHIN 57 BIT 11
DATA NO.: 13420-20-001

SHEET R6 OF 12






A Semal and Accomistac III.	THE PARTY WERE THANKING THAN	ONSULTING FNGINFFRS	T WASHINGTON DOTES	;
THE STATE OF THE S		CO	FWPO	

PROJECT:
STATE HIGHWAY 57 ACCESS IMPROVEMEN
EAGLE PUD & MILLE'S DEVELOPMENT PROJECT
PRIEST LAKE, BONNER COUNTY, IDAHO

FILE NAME: HONEY 57 HT 11
DATA No.: 13420-20-001

SHEET R7 OF 12




156


当 Associates A SEE

12-15-22 SCALE: AS SHOWN DRAWN BY CHECKED BY:

FILE NAME: HIGHERY 57 INT 1 DATA No.: 13420-20-001

SHEET R8 OF 12





ROAD CONSTRUCTION AND GRADING SPECIFICATIONS;

GENERAL — ROAD CONSTRUCTION SHALL CONFORM TO THE IDAHO TRANSPORTATION DEPARTMENT STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION (STANDARD SPECIFICATIONS) AND THE IDAHO STANDARDS FOR PUBLIC WORKS CONSTRUCTION (LATEST EDITION) (ISPWC). ALL MATERIALS SHALL CONFORM TO THE APPLICABLE SECTION OF THE STANDARD SPECIFICATIONS. IN THE EYENT OF A CODE CONFLICT, THE MORE RESTRICTIVE CODE SHALL APPLY.

CONSTRUCTION SCHEDULE - ROAD CONSTRUCTION SHALL BE COMPLETED THROUGH EXCAVATION, EMBANKMENT, AND ROUGH GRADING. THE UTILITY CONTRACTOR SHALL THEN BE ALLOWED TO COMPLETE ALL UTILITY CONSTRUCTION. ATTER UTILITY CONSTRUCTION IS COMPLETE, THE REMAINING ROAD CONSTRUCTION SHALL BE COMPLETED.

EXCESS EXCAVATION — EXCESS EXCAVATION SHALL BE PLACED WHERE DIRECTED BY THE OWNER OR ENGINEER.

EARTHWORK - EARTHWORK SHALL BE PERFORMED IN ACCORDANCE WITH SECTION 200
OF THE STANDARD SPECIFICATIONS. SUBGRADE SHALL BE CONSTRUCTED TO WITHIN

NEW ROADWAY CONSTRUCTION — NEW ROADWAY CONSTRUCTION, INCLUDING PREPARATION, PLACEMENT AND COMPACTION OF BASE, TOP COURSE, AND ASPHALT CONCRETE SUFFACING SHALL BE PERFORMED IN ACCORDANCE WITH APPLICABLE SECTIONS OF THE STANDARD SPECIFICATIONS (ISPWC) AND THE IDAHO TRANSPORTATION DEPARTMENT ROAD STANDARDS. THE ENGINEER SHALL BE NOTIFIED 24 HOURS IN ADVANCE OF SUBGRADE PREPARATION, BASE COURSE, AND TOP COURSE PREPARATION AND SHALL APPROVE ADEQUACY OF MATERIALS, PLACEMENT, AND COMPACTION ACCORDING TO THE REQUIRED SPECIFICATIONS.

GEOTEXTILE FABRIC — GEOTEXTILE FABRIC SHALL BE INSTALLED AT THE BASE OF THE ROCK CAP ROAD BALLAST ON ALL ROAD CONSTRUCTION. GEOTEXTILE FABRIC SHALL MEET THE REQUIREMENTS OF SECTION 718 OF THE STANDARD SPECIFICATIONS FOR TYPE II SEPARATION FABRIC. FABRIC PLACEMENT SHALL MEET THE REQUIREMENTS SET FORTH WITHIN SECTION 640 OF THE STANDARD SPECIFICATIONS.

BASE COURSE — BASE COURSE SHALL CONSIST OF 12—INCH COMPACTED THICKNESS ITD OF CLASS II OPEN GRADED ROCK BASE PER SECTION 703.08, COMPACTED TO 95% MAXIMUM DRY DENSITY OR ENGINEER APPROVED EQUAL.

TOP COURSE - TOP COURSE MATERIAL SHALL CONSIST OF 6-INCH COMPACTED THICKNESS OF ITD CLASS III OPEN GRADED ROCK BASE PER SECTION 703.08, COMPACT TO 95% PER ASTM D-1557

ASPHALT CONCRETE — ASPHALT CONCRETE SHALL CONSIST OF A COMPACTED THICKNESS INDICATED ON THE PLANS AND CONFORMING TO THE REQUIREMENTS FOR A CLASS I PLANT MIX OF DIVISION 800 OF THE ISPNCA. A REPRESENTATIVE OF THE ENGINEER AND IDAHO TRANSPORTATION DEPARTMENT SHALL BE NOTIFIED 24 HOURS PRIOR TO PLACEMENT OF ASPHALT AND SHALL HAVE THE OPPORTUNITY TO BE PRESENT AT PLACEMENT OF ASPHALT.

COMPACTION — IN PLACE COMPACTION TESTS TO VERIFY ACHIEVEMENT OF REQUIRED DENSITIES MUST BE PERFORMED ON ALL FILL AREAS INCLUDING SUBGRADE MATERIALS AND BITUMINOUS SURFACING AND SHALL BE SCHEDULED WITH THE ENGINEER PRIOR TO CONSTRUCTION. WITHIN THE ROAD PRISM AND FOUNDATION FOOTRINTS, ALL MATERIALS WITHIN 3 FEET OF THE FINISH GRADE SHALL BE COMPACTED TO 95% OF ASTM D1557 MOOFIED PROCTOR DEDNITY IN MAXIMUM 8 INCH LOOSE LITTS, ROAD SUBGRADE, EXISTING EXITH, AND ALL PLACED MATERIALS WITHIN THIS REAR MUST MEET 93% OF ASTM D1557 MODIFIED PROCTOR BELOW THREE FEET FROM FINISHED GRADE. EXRTH AND MATERIALS NOT MEETING THESE COMPACTION REQUIREMENTS MUST BE EXCANATED AND RECOMPACTED UNIT THE COMPACTION REQUIREMENTS MUST BE EXCONATED AND RECOMPACTED UNIT THE COMPACTION REQUIREMENTS AND SECOND AND SUBGRADE AND FILL WITHIN THE PIPE BEDDING MUST MEET 90% OF ASTM D1557 MODIFIED PROCTOR TO 6° BELOW PIPE INVERT.

INSPECTIONS - INSPECTIONS SHALL BE SCHEDULED WITH THE ENGINEER AT LEAST 24 HOURS IN ADVANCE. MINIMUM INSPECTION REQUIREMENTS:

1. COMPLETION OF ANY CONSTRUCTION SURVEYING AND STAKING.
2. COMPLETION OF TRAFFIC CONTROL DEVICES.
3. COMPLETION OF SUBGRADE, PRIOR TO THE PLACEMENT OF ANY BALLAST MATERIAL.
4. COMPLETION OF BALLAST, PRIOR TO PLACEMENT OF ANY TOP COURSE.

MATERIAL
COMPLETION OF INSTALLATION OF ROAD SIGNS, INSTALLATION OF ANY
APPURITEMANT STRUCTURES, AND RESEEDING OF DISTURBED AREA AND
SLOPES.

CONCRETE CURB - CONCRETE CURB CONSTRUCTION SHALL CONFORM TO THE REQUIREMENTS LISTED IN THE ISPWC DMSION 700.

CONCRETE SIDEWALKS — SHALL MEET DMISION 700 OF THE ISPWC, CLASS 3000, CAST IN PLACE CONCRETE CONSTRUCTION SHALL CONFORM TO THE MOST CURRENT ACI 318 CODE. CONCRETE EXPOSED TO WEATHER SHALL BE AIR BETTRAINED IN ACCORDANCE WITH THE MOST CURRENT ACI 318 SECTION 4.1 CODE. EXPOSED CONCRETE FACES SHALL BE GROUTED AND SACKED TO PRODUCE AN ARCHITECTURAL QUALITY SURFACE FINISH WITH NO WISIBLE VOIDS OR POCKETS.

SAW CUTTING — SAW CUTTING SHALL LEAVE A NEAT AND STRAIGHT EDGE. SAW CUT LOCATIONS SHALL BE PROTECTED FROM DAMAGE AND REMAIN IN SUITABLE CONDITION TO ACCEPT ADJACENT ASPHALT. ALL BROKEN EDGES SHALL BE RE—CUT TO ESTABLISH A NEAT LINE EDGE.

ROTOMILLING - ROTOMILLING SHALL BE COMPLETED IN ACCORDANCE WITH ITD ROAD CONSTRUCTION SPECIFICATIONS.

ROAD SPECIFICATIONS

STORMWATER SPECIFICATIONS:

GENERAL STORMWATER REQUIREMENTS - ALL EROSION AND SEDIMENT CONTROL METHODS AND STORMWATER MANAGEMENT PLAN CONSTRUCTION SHALL CONFORM TO THE RECUIREMENTS SET FORTH WITHIN THE STORMWATER MANAGEMENT PLAN FOR THE PROJECT AND THE "HAVIBOOK OF BEST MANAGEMENT PRACTICES FOR STORMWATER MANAGEMENT AND EROSION AND SEDIMENT CONTROL" (HAVIBOOK), AS PEPPARED FOR THE PANHANDLE MEALTH DISTRICT AND THE INTERPRISENCY STORMWATER COMMITTEE, AND THE IDAHO STANDARDS FOR PUBLIC WORKS CONSTRUCTION (LATEST EDITION) (ISPINC). ALL MATERIALS SHALL CONFORM TO THE APPLICABLE SECTION OF THE STANDARD SPECIFICATIONS. IN THE EVENT OF A CODE CONFLICT, THE MORE RESTRICTUTE CODE SHALL APPLY

EROSION AND SEDIMENT CONTROL DURING CONSTRUCTION — THE CONTRACTOR/DEVELOPER IS RESPONSIBLE FOR OBTAINING A STORMMATER NPOES PERMIT FOR CONSTRUCTION ACTIVITIES FROM THE EPA NATIONAL DISCHARGE ELIMINATION SYSTEM PROGRAM. EROSION AND SEDIMENT CONTROL SHALL BE ACCOMPLISHED AS NECESSARY THROUGH THE UNSTALLATION OF SILT FENCING AS SHOOM ON THE ATTACHED DRAWNINGS AND THROUGH THE USE OTHER METHODS AS NECESSARY, AS DESCRIBED IN CHAPTER M, "TEMPORUSOIL STABILIZATION" OF THE HANDBOOK. ALL METHODS SHALL BE IN ACCORDANCE WITH THE GUIDELINES AS DESCRIBED IN THE HANDBOOK.

OPERATION AND MAINTENANCE REQUIREMENTS — ALL TEMPORARY AND PERMANENT EROSION AND SEDIMENT CONTROL METHODS AND STORMWATER MANAGEMENT PLAN CONSTRUCTION SHALL BE MAINTENANCE PLAN WITHIN THE STORMWATER MANAGEMENT PLAN FOR THE PROJECT AS WELL AS THE MAINTENANCE REQUIREMENTS SET FORTH BY THE CITY. MAINTENANCE OF INFLITATION AREAS SHALL BE PERFORMED IN ORDER TO PROVIDE CONTINUED AND PRODUCTIVE GRASS GROWTH AND THE REMOVAL OF SEDIMENT AS NECESSARY TO ALLOW CONTINUED SOIL PERMEABILITY.

CONSTRUCTION ACTIVITIES — CONSTRUCTION ACTIVITIES SHALL BE SCHEDULED TO TAKE PLACE DURING SEASONAL LOW STREAM AND WETLANDS WATER LEVEL CONDITIONS, AND AS NEAR TO OPINIUM SOIL MOISTURE CONTENT AS POSSIBLE, IN ORDER TO MINIMIZE EROSION AND MAXIMIZE EFFECTIVENESS OF EROSION CONTROL MEASURES. CONSTRUCTION METHODS SHALL PROVIDE FOR ELIMINATING OR MINIMIZING DISCHARGES OF SEDIMENT, ORGANIC MATERIAL, OR TOXIC CHEMICALS.

TRENCH DEWATERING- ALL WATER GENERATED FROM TRENCH DEWATERING SHALL BE STORED AND TREATED ON SITE USING SWALES, SILT BAGS, OR OTHER MEANS APPROVED BY THE ENGINEER.

ALL DISTURBED AREAS AND GIAS SHALL BE REVEGETATED WITH NATIVE PLANTS AND GRASSES UPON COMPLETION OF CONSTRUCTION. SEED MIXTURE SHALL MEET THE REQUIREMENTS SET FORTH BY A PROFESSIONAL SOIL SCIENTIST OR LANDSCAPE ARCHITECT. THE FOLLOWING SEED MIXTURE SHALL BE ACCEPTABLE:

SPECIES	PERCENTAGE	LBS/ACRE DRILL SEEDED
CREEPING RED FESCUE	35%	8
HARD FESCUE	35%	8
COLONIAL BENTGRASS	21%	5
STRAWBERRY CLOVER	8×	2

EROSION AND SEDIMENTATION CONTROL STANDARD PLAN NOTES:

1. THE FOLLOWING CONSTRUCTION SEQUENCE SHALL BE FOLLOWED IN ORDER TO BEST MINIMIZE THE POTENTIAL FOR EROSION AND SEDIMENTATION CONTROL (ESC) PROBLEMS:
1.1. CLEAR AND GRUB SUFFICIENTLY FOR INSTALLATION OF TEMPORARY ESC BMPs
1.2. INSTALL TEMPORARY ESC BMPs, CONSTRUCTING SEDIMENT TRAPPHING BMPs AS ONE OF THE FIRST STEPS PRIOR TO GRADING;
1.3. CLEAR, GRUB AND ROUGH GRADE FOR ROUGS, TEMPORARY ACCESS POINTS AND UTILITY LOCATIONS;
1.4. STRAULZE ROUGHAY APPROACHES AND TEMPORARY ACCESS POINTS WITH THE APPROPRIATE CONSTRUCTION ENTIRY BMPs;
1.5. CLEAR, GRUB AND GRADE INDIVIDUAL LOTS OR GROUPS OF LOTS;
1.6. TEMPORARILY STRAULZE, THROUGH RE-VEGETATION OR OTHER APPROPRIATE BMPs, LOTS OR GROUPS OF LOTS IN SITUATIONS WHERE SUBSTANTIAL CUT OR FILL SLOPES
ARE A RESULT OF THE SITE GRADING;
1.7. CONSTRUCT OF THE SITE GRADING;

ARE A RESULT OF THE SITE GRADING;

1.7. CONSTRUCT ROADS, BUILDINGS, PERMANENT STORMANTER FACILITIES (I.e. INLETS, PONDS, UIC FACILITIES, ETG.);

1.8. PROTECT ALL PERMANENT STORMANTER FACILITIES (I.e. INLETS, PONDS, UIC FACILITIES, ETG.);

1.9. INSTALL PERMANENT SEC CONTROLS, WHEN APPLICABLE; AND,

1.10. REVIOUS ETMORRHY ESC CONTROLS, WHEN APPLICABLE; AND,

1.11. REVIOUS ETMORRHY ESC CONTROLS, WHEN APPLICABLE; AND,

2. PERMANENT ESC CONTROLS, WHEN APPLICABLE; AND (I.E. EXPLORED THE STALLED);

3. ALL LAND DISTURBING CATTMIES THAT HAVE THE POTENTIAL TO CAUSE EROSION OR SEDIMENTATION PROBLEMS HAVE CEASED; AND,

4. VEGETATION HAS BEEN ESTABLISHED IN THE AREAS NOTED AS REQUIRING VEGETATION ON THE ACCEPTED ESC PLAN ON FILE WITH THE LOCAL JURISDICTION.

5. INSPECT ALL ROLOWAYS, AT THE END OF THE DAY, ADJACENT TO THE CONSTRUCTION ACCESS ROUTE. IF IT IS EMPORT THAT SEDIMENT HAS BEEN TRACKED OFF SITE AND/OR BEYOND THE ROLOWAY APPROACH, CLEANING IS REQUIRED.

6. IF SEDIMENT REMOVAL IS RECESSARY PRIOR TO STREET WASHING, IT SHALL BE REMOVED BY SHOVELING OR PICKUP SWEEPING AND TRANSPORTED TO A CONTROLLED SEDIMENT DISPOSAL AREA.

1. IF STREET WASHING IS REQUIRED TO CLEAN SEDIMENT TRACKED OFF SITE, ONCE SEDIMENT HAS BEEN REMOVED, STREET WASHING WAS REQUIRED.

3. RESTORET WASHING IS REQUIRED TO CLEAN SEDIMENT TRACKED OFF SITE, ONCE SEDIMENT HAS BEEN REMOVED, STREET WASH WASTEWATER SHALL BE CONTROLLED BY PUMPING BACK ON—SITE OR OTHERWISE PROYENTED FROM DISCHARGING INTO SYSTEMS TRIBUTARY TO WAVERS OF THE STATE.

8. RESTORE CONSTRUCTION ACCESS ROUTE TO OR BETTER THAT THE PRE-CONSTRUCTION MOREDS FROM THE SITE (STORMWATER OR NON—STORMWAT DISCHARGE FROM THE SITE (STORMWATER OR NON—STORMWAT DISCHARGE FROM THE SITE (STORMWATER OR NON—STORMWAT DISCHARGE FROM THE SITE (STORMWATER OR NON—STORMWAT

8. RESTORE CONSTRUCTION ACCESS ROUTE TO OR BETTER THAT THE PRE-CONSTRUCTION CONDITION.

9. RETAIN THE DUFF LAYER, NATIVE TOPSOIL, AND NATURAL YEGETATION IN AN UNDISTURBED STATE TO THE MAXIMUM EXTENT PRACTICAL.

10. INSPECT SEDIMENT CONTROL BUPS WERKLY AT A MINIMUM, DAILY DURING A STORM EVENT, AND ATTER MAY DISCHARGE FROM THE SITE (STORMWATER OR NON-STORMWATER). THE INSPECTION FREQUENCY MAY BE REDUCED TO ONCE A MONTH IF THE SITE IS STANLED AND INJURIED.

11. CONTROL FUGITIVE DUST FROM CONSTRUCTION ACTIVITY IN ACCORDANCE WITH THE STATE AND/OR LOCAL AIR QUALITY CONTROL AUTHORITIES WITH JURISDICTION OVER THE PROJECT AREA.

12. STABILIZE EXPOSED UNWORKED SOILS (INCLUDING STOCKPILES), WHETHER AT FINAL GRADE OR NOT, WITHIN 10 DAYS DURING THE REGIONAL DRY SEASON (JULY 1 THROUGH SEPTEMBER 30) AND WITHIN 5 DAYS DURING THE SEASONAL WET SEASON (OCCORDER 1 THROUGH JUNE 30). SOILS MUST BE STABILIZED AT THE EDU OF 4 SHITT BEFORE A HOUDAY WEEKEND IF NEEDER BASED ON THE WEATHER FORECAST. THIS TIME LIMIT MAY ONLY BE ADJUSTED BY A LOCAL JURISDICTION WITH A "QUALIFIED LOCAL PROGRAM", IF IT CAN BE DEBNOSTRATED THAT THE RECENT PRECIPITATION JUSTIFIES A DIFFERENT STANDARD AND MEETS THE REQUIREMENTS SET FORTH IN THE CONSTRUCTION STORMWATER GENERAL PERMIT.

13. PROTECT INLETS REPROVED, ACTION HAVE STORMWATER MANAGEMENT FACILITIES FROM SEDIMENT, WHETHER OR NOT FACILITIES ARE OPERABLE.

14. KEEP ROADS ADJACENT TO INLETS CLEAN.

15. INSPECT INLETS WERKLY AT A MINIMUM AND DAILY DURING STORM EVENTS.

16. CONSTRUCT STORMWATER CONTROL OF PROVIDED SOIL PROPOSED. STORMWATER GENERAL PERMIT.

17. STOCKPILE MATERIALS (SUCH AS TOPSOIL) ON SITE, KEEPING OFF OF ROADWAY AND SIDEWALKS.

18. COVER CONTROL ON PROTECT ALL CHEMICALS, LOUDD PRODUCTS, PETTOLIUM PRODUCT, SHO NON-INERT WASTES PRESENT ON SITE FROM VANDALISM (SEE CHAPTER 173-3-94 WAG FOR THE DETHINION OF INERT MASTE, USE SECONDARY CONTAINMENT FOR ON-SITE FULLING TANKS.


19. CONDOLV MAINTENANCE AND PROTECT ALL CHEMICALS, USUAL PROPOSOT. SHOULDS FOR PASS, OUT AND DEPARLS, SOLVENT AND DE-GREASING O

CHEMICALS INTO STORMWATER RUNOFF FACILITIES, AMEND MANUFACTURER'S RECOMMENDED APPLICATION RATES AND PROCEDURES TO MEET THIS NECESSARY. NECESSARY.

21. INSPECT ON A REQUIAR BASIS (AT A MINIMUM WEEKLY, AND DAILY DURING/AFTER A RUNOFF PRODUCING STORM EVENT) AND MAINTAIN ALL EROSION AND SEDMENT CONTROL BMPs TO ENSURE SUCCESSFUL PERFORMANCE OF THE BMPs NOTE THAT INLET PROTECTION DEVICES SHALL BE CLEANED OR REMOVED AND REPLACED BEFORE SIX INCHES OF SEDIMENT CAN ACCUMULATE.

22. REMOVE TEMPORARY (SC BMPs WITHIN 30 DAYS AFTER THE TEMPORARY BMPs ARE NO LONGER NEEDED. PERMANENTLY STABILIZE AREAS THAT ARE DISTURBED DURING THE REMOVAL PROCESS.

STORMWATER SPECIFICATIONS N.T.S.



TEMPORARY GRAVEL CONSTRUCTION ENTRANCE DETAIL

PLAN

ENGINEER'S STAME

56

Z NEWP

HIGHWAY 57 ACCESS IMPROVEMENTS PUD & MILLIE'S DEVELOPMENT PROJECT LAKE, BONNER COUNTY, IDAHO

DETAILS

Z


24

三名 STATE PEAGLE PRIEST

DATE: 12-15-22 SCALE: AS SHOW DRAWN BY KAH CHECKED BY: KA

FILE NAME: HOHBY 57 MT # DATA No.: 13420-20-001

SHEETR100F 12



ENGINEER'S STAMP


CONSULTING ENGINEERS
EWPORT, WASHINGTON, 99156
(509) 447—3626

AFFIC CONTROL PLAN NECT:

DATE: 12-15-22
SCALE: AS SHOWN
DRAWN BY: KAK

CHECKED BY: KAK FILE NAME: HONEY 57 NT ri DATA No.:13420-20-001

SHEET R1 10F 12





SS 29156 T 5/30 REVISED ENTRANCE ROADDLO/KAK AND DATE REVISION DRN/CHK

SONSULTING ENGINEERS CONSULTING ENGINEERS NEWPORT, WASHINGTON, 99156 (509) 447–3626



EROSION & SEDIMENT CONTROL PLAN

TEMPORARY EROSIC
PROJECT:
STATE HIGHWAY 57

DATE: 12-15-22
SCALE: AS SHOWN
DRAWN BY: KAK
CHECKED BY: KAK
FILE NAME: HORNEY 57 NT rt

DATA No.:₁₃₄₂₀₋₂₀₋₀₀₁

SHEETR120F 12